Benefits of Expanded Modularization For Ship Design & Construction EM-GD-010

January 2022



PERCEPTION is a registered trademark of SPAR Associates, Inc. ESTI-MATE, MAT-PAC, WORK-PAC, and PERT-PAC are trademarks of SPAR.

PERCEPTION®

Trade Secrets and Proprietary Properties
Of
SPAR Associates, Inc.
Annapolis, MD 21403

NOTICE

The information contained in this document is subject to change without notice.

SPAR ASSOCIATES, INC. MAKES NO WARRANTY OF ANY KIND WITH REGARD TO THIS MATERIAL, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE.

SPAR Associates, Inc. shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

This document contains proprietary information, which is protected by copyright. All rights reserved. No part of this document may be photocopied, reproduced or translated to another program language without prior written consent of SPAR Associates, Inc.

Contents

Contents	4
1.0 Introduction	
2.0 Modern Shipbuilding Build Strategies	8
3.0 Modular Construction	
4.0 Outfitted Hull Block Construction	. 11
5.0 Shipbuilding Modules	
5.1 New Construction Benefits:	. 17
5.2 Ship Maintenance Benefits:	. 17
5.3 Ship Operations Benefits:	. 17
6.0 SPAR Cost Model	. 19
6.1 Flexible Hull Structures Modeling.	
6.2 Flexible Powering Options	. 19
6.3 Automated Cost Adjustments	20
6.4 Cost Estimating Relationships	20
6.5 Shipyard Productivity Factors	21
6.6 Costing & Pricing	
6.7 Transport Factor	. 22
6.8 Cost Risk	23
6.9 Estimated Manpower Requirements	
6.10 Design Trade-Off Studies	23
7.0 Baseline Corvette	
7.1 Baseline Corvette Build Strategy Scenarios	
7.2 Baseline Cost Year	
7.3 Labor Pricing	28
7.4 Profit	
7.5 G&A Costs	
7.6 Non-Recurring & Support Services	
7.6.1 Non-Recurring Costs	
7.6.2 SWBS 800 Recurring Technical Support	
7.6.3 SWBS 900 Recurring Production Services	. 32
7.7 Shipbuilding Productivity	
7.8 Module Builders	
7.9 Series Ship Production Estimates	
7.9.1 Labor Cost Learning	
7.9.2 Material Cost Learning	
7.10 Schedules	
7.11 Estimated Freight Costs	
7.12 Margin	
7.13 Change Orders	46
7.14 Program Cost	
8.0 Cost & Schedule Savings from Modular Construction	
9.0 Cost & Schedule Savings from Modularized Weapons Systems	
10.0 Reduced Cost Risk?	65

10.1 Production Schedule Risk	68
10.2 Engineering Performance Risk	69
10.3 Shipyard Experience Risk	69
10.4 Engineering/Production Overlap Rework Risk	69
10.5 Estimate CER Cost Risk	70
10.6 Cost Risk Allocations to Series Ship Programs	70
11.0 Conclusions	
11.1 Focus on Engineering Reform/Revival	73
11.2 Focus on Rebuilding Shipbuilding Worker and Management Skills	74
11.3 Focus on Minimizing Change Design Changes after Production Has Begun.	74
11.4 Focus on Sharing Cost Risk	75
11.5 Reasons for Outsourcing Cost Efficiencies	75
11.6 Focus on Improving Planning & Project Management Skills	76
11.7 Measure Performance	
Appendix I: Cost Estimate Summaries	78
Appendix II: Cost Risk	83
III.1 Cost Risk of the Production Estimate Data	84
III.2 Predicting Production Overlap Rework Costs	
III.3 Estimating Cost Risk of Overlap Rework	88
III.4 Estimating Cost Risk of Shipbuilder Inexperience	90
III.5 Estimating Cost Risk of Engineering Quality	93
III.6 Estimating Cost Risk Due to Tight Production Schedule	96
III.7 Cost Risk on Follow Ship Programs	97

1.0 Introduction

Cost and schedule benefits from modular construction are nothing new, and these manufacturing and assembly approaches are being successfully implemented not only by foreign shipbuilders, but also by aircraft, automobile and home appliance industries. There have been many different studies made within and without the U.S. that predict significant cost and schedule savings. The Maritech Modular Tanker Consortium is but one research project that focused on developing a variety of equipment modules such as for the main propulsion plant. Other areas of successful modularization have been achieved with modular accommodations cabin units extensively used in the cruise ship building process. The U.S. Navy also portrayed savings from its "Affordability through Commonality" program.

Modular construction allows what is called early stage construction benefits. Examples of early stage construction in shipbuilding include on-unit and on-block outfitting. As opposed to on-board work, these on-shore stages allow workers direct and easy access to the work site (the block or unit) and the convenience of working under cover and where tools, equipment and material requirements are more readily available.

There are a number of rules of thumb that have been applied to estimate the savings. Labor costs on board can be 3-5 times higher than equivalent work done in the shop or on the platen. The figure below approximates further these savings across a variety of manufacturing and assembly stages of construction.

Stage	MHRS per Unit of Work
Panel	1
	<u> </u>
Sub-Assembly	1
Module	1
Unit	2
Block	4
Paint Cell	4
Mega-Block	6
Berth	8
Quay	12

Figure 1-1: Potential Levels of Productivity¹

Actual shipbuilding production data clearly reveals how these savings affect the costs of various ship systems such as piping, HVAC, and others. Insight from this information was used to assist RAND Corp document² for the British Ministry of Defence the potential savings from using these methods of construction.

This document contains intellectual properties copyrighted by SPAR Associates, Inc.

¹ "More Effective Planning of Early Ship Outfitting," G.J. Bruce & T. Nielsen, presented to The Society of Naval Architects and Marine Engineers.

² "Productivity in Shipbuilding," L.C. Deschamps, SPAR Associates, Inc. as reported to RAND Corporation, April 2003.